

DRAFT TENDER SCHEDULE


Issued to :


Original / Duplicate
Item No.Name of the Work: Maintenance of Ward and Emergency Works in Ward
(Kuvempunagara), Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	
1	24.84	Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	105.84	
2	3.24	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4847.04	
3	34.56	Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4773.60	
4	51.20	Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	92.88	
5	7.80	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5327.64	



 Executive Engineer
 Byatarayanapura Division
 Yelahanka Zone, B.B.M.P.
 Bangalore - 560 092

6	23.15	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal , coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplasticiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, etc complete as per specifications and directions of engineer in charge of the work	Cum	6065.28	
7	18.52	Providing mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work	Qtl	7975.80	
8	92.38	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness , including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	292.68	
9	20	1031 - Hire Charges of J.C.B Excavator including Operator and Fuel (P. XXXXVII/I. 23) etc complete as per specifications and directions of engineer in charge of the work	Day	6720.00	
10	70	1024 - Hire Charges of Tractor 40 HP including Operator and Fuel (P. XXXXVII/I. 19) etc complete as per specifications and directions of engineer in charge of the work	Day	2240.00	
11	700	Engaging Causal Labours (Unskilled mazdoor Heavy) etc complete as per specifications and directions of engineer in charge of the work	Nos	223.93	
12	23.60	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	73.57	


Signature of the Contractor


Executive Engineer
Byatarayanapura D
BBMP, Bangalore

ಕರಡು ಬಂದರೆ ಸಹಜವಾಗಿ
ಬಿಡುಗಡೆ ಮಾಡಿ, ನೀಡಿ
ಬಿಡುಗಡೆ ಮಾಡಿ/ಇಲ್ಲದಿದ್ದರೆ
ಅವಕಾಶವಿದೆ ನೀಡಲಾಗಿದೆ


Superintending Engineer
Kalyanahalli Zone
BBMP, Bangalore